

**Sitapur Eye Hospital Trust branch Indira Gandhi, Sitapur Eye Hospital, Lucknow**

**EHS/Tender Notification/2015**

**29<sup>th</sup> Dec, 2015**

<b>S.No.(1)</b>	<b>Particular of work (2)</b>	<b>Quantity(3)</b>	<b>Unit (4)</b>	<b>Rate (5)</b>	<b>Amount (6)</b>
<b>1.</b>	<b>(B) False Ceiling work</b> I. Providing & fixing false ceiling with Armstrong false ceiling with GI frame/aluminum frame hanging from main roof with GI wire are strip as desirable height with all material (as approved by department) labour tool & plant complete and also including for fixing of light and fan fixtures etc complete as required for proper completion of work.	207.43	Sqm		
<b>2.</b>	<b>© Flooring work</b> I. Dismantling of existing plaster including disposal of refuse materials as directed by engineer incharge within a distance of 60 meter.	826.55	Sqm		
	II. Providing & laying (White or colored ) Kajaria tiles Romano tiles are equivalent in flooring or in skirting or dado laid with 1:3 cement & approved courses and mortar finished with white cement ( or color pigment). Slurry jointing with cement polished complete including supply of all materials, labour tool & plant required for proper completion of work.	671.73	Sqm		
	III. Providing & fixing (white or colored) Kajaria or equivalent floor vitrified tiles of size 2X2' over 20 to 25 mm thick base of cement mortar with 1:4 & jointing grouting finishing with color pigment is required etc. complete as per drawing and specification including all material, labour tool & plants required for proper completion of work.	350.00	Sqm		
<b>3.</b>	<b>(D) Plaster &amp; pointing</b>	154.82	Sqm		

	I. 12 mm thick plaster with cement mortar in proportion of 1:3 cement & fine sand of FM 1.25 including all labour, material, T&P etc required for proper completion of work.				
	II. 15 mm thick plaster with cement & fine sand FM 1.25 mortar including all labour, materials T & P required for proper completion of work.	267.37	Sqm		
4.	<b>(E) Brick Work</b> I. Class 150 brick work in 1:6 cement & fine sand of 1.25 fineness modulus in supper structure above plinth level upto floor two level including necessary cutting and molding of brick work as required and also including hency combed brick in thickness of wall more than 12 cm.	2.5	Cum		
5.	<b>(F) Mild steel and Iron work</b> I. Mild steel or iron work in heavy size such as trusses, build up gates, record racks, roof work, gates etc. wrought to required for including drilling holes rebating or Belding where necessary and their fixing required for proper completion of work.	1.5	Qtl		
6.	<b>(G) Painting &amp; distempering</b> I. Applying priming coat with two or more coat over new/old steel and wood & other metal surfaces upto 10 cm in width or girth or small articles not exceeding 0.10 sq. area after and including preparing the surface by thoroughly cleaning oil, grease, dirt, and other foreign matter and scoured with wire brushes, fine steel wood scrapper and papering and knotting including cost of all materials, labour, T & P etc required for proper completion of work.	75	Sqm		
	II. Applying extra over items as in 7 (II) above but surface over 10 cm width or girth.	249.8	Sqm		
	III. Wall painting one coat with plastic emulsion apex exterior paint of approved brand and manufacturer on decorative wall surface to give an even said including	474.75	Sqm		

	thoroughly brushing the surfaces clean of all dirt grease, loose pieces and prepare smooth.				
	<b>IV.</b> Extra over items above and for every subsequent coat of wall painting with same paint of approved brand and manufacturer.	474.75	Sqm		
	<b>V.</b> Providing and applying one or two coat of plastic emulsion paint apex exterior (weather coat) above the surfaces with of approved brand and manufacturer to give an even said including thoroughly brushing the surfaces clean of all dirt grease, loose pieces and prepare smooth.	372.87	Sqm		
<b>7.</b>	<b>(H). Aluminum work</b> <b>I.</b> Supply & fixing of aluminum anodized window or partition having 2 mm thick aluminum section including coating and an average coating of 20 micron fully glazed made of aluminum door tube size 83.5X44.65 mm as vertical member and 114.0X44.45 mm size tube in bottom and horizontal member door chaukhat should be of aluminum tubular vertical with two open able shutter the rates will including cost of materials fixtures 5 mm glass in part and ACP seat handles locks screw and necessary bending and excluding the cost of floor spring if required for the proper completion of work as per drawing, design and direction of EIC.	52.35	Sqm		
<b>8.</b>	<b>(I) Miscellaneous</b> <b>I.</b> Finishing of walls/ Ceiling by plaster of Paris/Birla putty 1 mm thick of approved make (JK R Birla) as required including supply of all labour, T & P required for proper completion of work.	629.07	Sqm		
	<b>II.</b> Dismantling of collapsible ms gates, windows etc.	2 Nos.	Job work		
	<b>III.</b> Repairing of door window wooden work including all materials, labours, T & P etc required for proper completion of work.	10 Nos.	Job work		

**Note: - Contractor - Please fill column No. 5 & 6 (rate & Amount). All quantity is variable.**

- **Tender cost Rs. 1000/- in the favor of “Secretary Sitapur Eye Hospital Trust” Sitapur by demand draft.**
- **Security money Rs. 2, 14,100/- will be deposited in the favor of “Secretary Sitapur Eye Hospital Trust” Sitapur by demand draft.**
- **Completion period- 6 months**

**Terms & Conditions:-**

- Assets of bidding documents may be downloaded from our website [www.sitapureyehospital.org](http://www.sitapureyehospital.org) corresponding to the respective work from 30<sup>th</sup> Dec, 2015 to 13<sup>th</sup> Jan, 2016.
- Cost of tender Rs. 1000/-(demand draft) in the favor of “Secretary Sitapur Eye Hospital trust” Sitapur along with the tender which will be non refundable & security money Rs.2, 14,100/-(DD) in the favour of “Secretary Sitapur Eye Hospital Trust”, Sitapur (Refundable).
- Completion period of work 6 months.
- The CMO, Eye hospital Sitapur reserve the right to postponed/recall/cancel one or all the tenders without assigning any reason.
- The security money will be refunded after 6 months from the date of completion of the satisfactory work.
- If the work is not completed within the said time & work is not upto the mark then security money may be forfeited.
- Registration certificate of the contractor to be submitted.
- Character certificate & Identity proof of the contractor to be submitted.
- Detailed specifications of the work of each schedule items are applicable as per norms of UP PWD schedule.
- Any item of the said work can be deleted as per site incharge.

- The tender must be delivered to the Office of the Chief Medical Officer, Sitapur Eye Hospital, Sitapur U.P. in a sealed & separate envelope as required work on or before 13<sup>th</sup> Jan, 2016 upto 12:30 PM & the tender will be opened on 13<sup>th</sup> Jan, 2016 at 3:30 PM in the office of the CMO, Sitapur Eye Hospital, Sitapur U.P. in the presence of the bidders who wish to attend. If the office happens to be closed on the date of receipt or opening of the tender as specified the bids will be received & open on the next working day respectively at the same time and venue.
- In the case of any dispute jurisdiction will be settled in civil or Dist. Court Sitapur U.P. only.
- The bidders/contractor will quote their rates and amount in column no. 5 & 6.
- Signature of the contractor along with the seal is mandatory on each submitted page.

**Chief Medical Officer**

**Sitapur Eye Hospital, Sitapur U.P.**