

Tender for Sewerage system & building repair/renovation work at Haldwani Branch, Sitapur Eye Hospital, Uttrakhand.

EHS/2015/Tender Notification

29th Dec, 2015

S.No.	Particular of work	Quantity	Unit	Rate	Amount
01.	02.	03.	04.	05.	06.
1.	Earth work in excavation in trenches for foundation, pipe & cable etc. including lift upto 1.5 meter and lead upto 50 meter & dressing of sites and ramming of bottom & disposal of surplus excavated earth as per directed by EIC within a lead of 50 meter.	375	Cum		
2.	Dismantling of existing sewer line including soil and pipe as an where required including stacking of material as directed by EIC with a distance of 60 meter	300	RMT		
3.	Providing and laying ECC work in foundation trenches with 1:4:8 1 Cement 4 fine sand and 8 25 mm size brick blast including ramming consolidation frame work complete as per site and direction of EIC complete in all respect including all labours/materials/T & P required for proper completion of work.	22.5	Cum		
4.	Providing & laying cement concrete 1:2:4 one cement 2 coarse sand and 4 graded stone blast 12 mm nominal size including supply of all materials/labours & T & P etc required for proper completion of work and curing complete also including cost of form work in foundation and floor	11.25	Cum		
5.	Construction of Main hole with RCC top slab 1:2:4 mix foundation concrete 1:4:8 mix inside plaster 15 mm thick with cement mortar 1:3 one cement 3 fine sand	6	Nos.		

	with a floating coat neat cement and making channels in cement concrete 1:2:4 mix finished smooth including curing and testing. (A) Inside size 1 meterX1 meterX2.5 meter				
6.	Construction of Main hole with RCC top slab 1:2:4 mix foundation concrete 1:4:8 mix inside plaster 15 mm thick with cement mortar 1:3 one cement 3 fine sand with a floating coat neat cement and making channels in cement concrete 1:2:4 mixes finished smooth including curing and testing. (A) Inside size .450X450X600	13	Nos.		
7.	Providing and fixing PVC heavy gaze pipeline (6 KGF) including all fitting fixtures complete including all labour/material T & P required for proper completion of work (A) 100 mm dia (B) 150 mm dia (C) 200 mm dia (D) 75 mm dia	50 meter 150 meter 100 meter 300 meter	RMT		
8.	Filling of available excavated earth in trenches, plinth, side of foundation etc. in layer not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering complete.	300	Cum		
9.	. 15 mm thick plaster with cement & fine sand FM 1.25 mortar including all labour, materials T & P required for proper completion of work	300	Sqft		
10.	Disposable of surplus soil and dismantle material from the hospital premises to outside of the municipal area including all cortege/loading unloading material T & P etc required for proper completion of work	100	Cum		
11.	Making of connection of drain or sewer line with existing main hole including breaking into and making	19	Nos		

	good the walls floors with cement concrete 1:2:4 cement plastered on both side with cement mortar 1:3 finished with a floating coat of neat cement and making necessary channels with cement concrete complete.				
12.	25 mm thick cement concrete flooring 1:2;4 one cement 2 core sand 4 graded stone aggregate of size 12.5 mm and below laid over the base concrete and finished with floating coats of neat cement including fixing of glass strips including all labours/materials/T&P required for proper completion of work.	35	Sqm		
13.	Dismantling cement concrete or brick or granolithic floor including stacking of dismantled material as directed by EIC with in a distance of 50 meter	50	Sqm		
14.	Providing & fixing plain GI 22 gaze Patnala for rain water including required iron hook of 10 mm dia complete in all respect of required shape & size for sloppy roof including all materials/labour T & P required for proper completion of work.	130	RMT		
15.	Providing & fixing rain water down pipe with funnel of 20 gaze GI sheet 8 feet height complete in all respect as per the direction of EIC including labour/material & T&P etc.	8	Nos.		
16.	25 mm thick cement concrete flooring 1:2;4 one cement 2 core sand 4 graded stone aggregate of size 12.5 mm and below laid over the base concrete and finished with floating coats of neat cement including fixing of glass strips including all labours/materials/T&P required for proper completion of work (excluding base concrete)	200	Sqm		
17.	Dismantling of existing plaster including disposal of refuses as directed by EIC with a distance of 50 meter.	300	Sqmt		
18.	Dismantling of door, windows, ventilators, shutters including chaukat with hole fause complete in all respect	35	Sqm		
19.	Dismantling of sundried brick work including stacking of	5	Cum		

	dismantled material as directed by EIC within a distance of 60 meter.				
20.	Brick work 100 50 class in 1:6 cement & sand mortar in super structure for one brick wall including supply of all materials/labour T & P etc. complete in all respect	30	Cum		
22.	Same as above item no. 25 but wall thickness 120 mm half brick wall with 1:4 one cement 4 sand	600	Cum		
23.	12 mm thick plaster in cement mortar 1:6 including supply of all materials/labours T & P etc as required for the completion of work	600	Sqm		
24.	Proving & fixing Sal wood rought framed as fixed I/C simple stat work as in Chaukat including supply of all material/labour T & P required for the proper completion of work	1.4	Cum		
25.	Supply & fixing of 40 mm thick Sisam wood fully paneled door & windows shutter including supply fixing of hinges, locking arrangement such as nuts, volts, handles, tower volts L- drops water proof shutters etc. complete in all respect, including all labour/materials T&P required for proper completion of work in all respect.	20	Sqmt		
26.	Providing & fixing MS Iron fabricated grill as per design & size including labour/material T & P etc.	12	Qtl		
27.	Providing & fixing false ceiling with 12 mm thick gypsum board with GI frame/aluminum frame hanging from main roof with GI wire are strip as desirable height with all material (as approved by department) labour tool & plant complete and also including for fixing of light and fan fixtures etc complete as required for proper completion of work.	75	Sqm		
28.	H). Aluminum work I. Supply & fixing of aluminum anodized door or window or partition having 2 mm thick aluminum section including coating and an average coating of 20 micron	120	Sqmt		

	fully glazed made of aluminum door tube size 83.5X44.65 mm as vertical member and 114.0X44.45 mm size tube in bottom and horizontal member door chaukhat should be of aluminum tubular vertical with two open able shutter the rates will including cost of materials fixtures 5 mm glass in part and ACP seat handles locks screw and necessary bending and excluding the cost of floor spring if required for the proper completion of work as per drawing, design and direction of EIC.				
29.	Finishing of walls with 2 coat of water proof cement paint of approved quality on previously old treated surface with this paint to give and even said after thoroughly brushing the surface to remove all dirt and remains loose power, materials including curing cost of all material/labour & T&P required for completion of work.	2000	Sqmt		
30.	<p>) Painting & distempering</p> <p>I. Applying priming coat with two or more coat over new/old steel and wood & other metal surfaces upto 10 cm in width or girth or small articles not exceeding 0.10 sq. area after and including preparing the surface by thoroughly cleaning oil, grease, dirt, and other foreign matter and scoured with wire brushes, fine steel wood scrapper and papering and knotting including cost of all materials, labour, T & P etc required for proper completion of work.</p> <p>II. Applying extra over items as in 7 (II) above but surface over 10 cm width or girth.</p> <p>III. Wall painting one coat with plastic emulsion apex exterior paint of approved brand and</p>	<p>875</p> <p>500</p> <p>2900</p>	<p>Sqmt</p> <p>Sqmt</p> <p>Sqmt</p>		

	<p>manufacturer on decorative wall surface to give an even said including thoroughly brushing the surfaces clean of all dirt grease, loose pieces and prepare smooth.</p> <p>IV. . Extra over items above and for every subsequent coat of wall painting with same paint of approved brand and manufacturer.</p> <p>V. Same as above serial no. roman I but above CGI roof over 10 cm wirth or girth</p>	2900	Sqmt		
31.	<p>Providing and laying brick coba 12 mm thick laid with M 150 class brick bat coba 7.5 cm thick with gap of 15 mm to each other over 20 mm thick base of cement mortar 1:4 cement & course sand mix with water proofing compound spreading cement slurry mix with aerelic cement concrete water proofing compound filled gap of coba and top of coba mortar mix with water proofing compound in 1:4 cement & course sand and mortar finished smooth and top matched false square 30 cmX30 cm & side wall paraet shall be monolithic palster wall upto 30 cm higher & junction and corner shall be rounded by big blast cement & course sand machinery coba with top finished plaster mix with aeretic water proofing compound @ 2% by weight and including supply of all materials/labours and T& P etc. complete for proper completion of work</p>	200	Sqm		
44.	<p>Electrification work, PowerPoint, light & fan point etc. as per requirement.</p>		Each point.		

Note: Quantity of the work may be vary

Terms & Conditions:-

- Assets of bidding documents may be downloaded from our website www.sitapureyehospital.org corresponding to the respective work from 30th Dec, 2015 to 13th Jan, 2016.
- Cost of tender Rs. 1000/- (demand draft) in the favor of “Secretary Sitapur Eye Hospital trust” Sitapur along with the tender which will be non refundable & security money Rs.3, 00000/- (DD) in the favour of “Secretary Sitapur Eye Hospital Trust”, Sitapur (Refundable).
- Completion period of work 6 months.
- The CMO, Eye hospital Sitapur reserve the right to postponed/recall/cancel one or all the tenders without assigning any reason.
- The security money will be refunded after 6 months from the date of completion of the satisfactory work.
- If the work is not completed within the said time & work is not upto the mark then security money may be forfeited.
- Registration certificate of the contractor to be submitted.
- Character certificate & Identity proof of the contractor to be submitted.
- Detail specifications of the work of each schedule items are applicable as per norms of Uttarakhand PWD schedule.
- Any item of the said work can be deleted as per site incharge.
- The tender must be delivered to the Office of the Chief Medical Officer, Sitapur Eye Hospital, Sitapur U.P. in a sealed & separate envelope as required work on or before 13th Jan, 2016 upto 12:30 PM & the tender will be opened on 13th Jan, 2016 at 3:30 PM in the office of the CMO, Sitapur Eye Hospital, Sitapur U.P. in the presence of the bidders who wish to attend. If the office happens to be closed on the date of receipt or opening of the tender as specified the bids will be received & open on the next working day respectively at the same time and venue.
- In the case of any dispute jurisdiction will be settled in civil or Dist. Court Sitapur U.P. only.
- The bidders/contractor will quote their rates and amount in column no. 5 & 6.
- Signature of the contractor along with the seal is mandatory on each submitted page.

Chief Medical Officer

Sitapur Eye Hospital, Sitapur U.P.